Results of Borehole Geophysical Logging and Aquifer-Isolation Tests Conducted in the John Wagner and Sons, Inc. Former Production Well, Ivyland, Pennsylvania

> U.S. GEOLOGICAL SURVEY Water-Resources Investigations Report 97-4095



PREPARED IN COOPERATION WITH THE

U.S. NAVY

Results of Borehole Geophysical Logging and Aquifer-Isolation Tests Conducted in the John Wagner and Sons, Inc. Former Production Well, Ivyland, Pennsylvania

BY RONALD A. SLOTO

U.S. GEOLOGICAL SURVEY Water-Resources Investigations Report 97-4095



PREPARED IN COOPERATION WITH THE U.S. NAVY

Lemoyne, Pennsylvania 1997

U.S. DEPARTMENT OF THE INTERIOR

BRUCE BABBITT, Secretary

U.S. GEOLOGICAL SURVEY

Gordon P. Eaton, Director

For additional information write to:

District Chief U.S. Geological Survey 840 Market Street Lemoyne, Pennsylvania 17043-1586 Copies of this report may be purchased from:

U.S. Geological Survey Branch of Information Services Box 25286 Denver, Colorado 80225-0286

CONTENTS

| Abstract |
|--|
| Introduction |
| Results of borehole geophysical logging |
| Results of aquifer-isolation tests |
| Aquifer-isolation test of zone 1 (248 to 496 feet below floor level) |
| Aquifer-isolation test of zone 2 (223 to 248 feet below floor level) |
| Aquifer-isolation test of zone 3 (198 to 223 feet below floor level) |
| Aquifer-isolation test of zone 4 (81 to 106 feet below floor level) |
| Aquifer-isolation test of zone 5 (57 to 81 feet below floor level) |
| Summary and conclusions |
| References cited |

ILLUSTRATIONS

| 1. Map showing the location of the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania | 2 |
|--|----|
| 2. Borehole geophysical logs from the John Wagner and Sons, Inc. former production well. | 3 |
| 3. Caliper log and borehole-flow measurements, John Wagner and Sons, Inc. former production well | 5 |
| 4. Generalized sketch of straddle-packer assembly and pump in borehole | 6 |
| 5. Caliper log showing zones isolated in the John Wagner and Sons, Inc. former production well | 7 |
| 6-10. Hydrographs from aquifer-isolation test of: | |
| Zone 1 (248 to 496 feet below floor level) in the John Wagner and Sons, Inc. former production well. | 9 |
| Zone 2 (223 to 248 feet below floor level) in the John Wagner and Sons, Inc. former production well. | 11 |
| 8. Zone 3 (198 to 223 feet below floor level) in the John Wagner and Sons, Inc. former production well | 13 |
| 9. Zone 4 (81 to 106 feet below floor level) in the John Wagner and Sons, Inc. former production well | 15 |
| 10. Zone 5 (57 to 81 feet below floor level) in the John Wagner and Sons, Inc. former production well | 17 |

TABLES

| 1. Summary of heatpulse-flowmeter measurements made in the John Wagner and Sons, Inc. former production well |
|---|
| 2. Intervals isolated in the John Wagner and Sons, Inc. former production well |
| 3. Pumpage from and specific capacity of isolated zones in the John Wagner and Sons, Inc. former production well |
| 4. Schedule and pumping rates for the aquifer-isolation test of zone 1 (248 to 496 feet below floor level) in the John Wagner and Sons, Inc. former production well, December 12, 1996 |
| 5. Schedule and pumping rates for the aquifer-isolation test of zone 2 (223 to 248 feet below floor level) in the John Wagner and Sons, Inc. former production well, December 13, 1996 |
| 6. Schedule and pumping rates for the aquifer-isolation test of zone 3 (198 to 223 feet below floor level) in the John Wagner and Sons, Inc. former production well, December 13, 1996 |
| 7. Schedule and pumping rates for the aquifer-isolation test of zone 4 (81 to 106 feet below floor level) in the John Wagner and Sons, Inc. former production well, December 16, 1996 |
| 8. Schedule and pumping rates for the aquifer-isolation test of zone 5 (57 to 81 feet below floor level) in the John Wagner and Sons, Inc. former production well, December 16, 1996 |

CONVERSION FACTORS

| MULTIPLY | <u>BY</u> | TO OBTAIN |
|---|-------------------|----------------------------|
| | LENGTH | |
| inch (in.) | 25.4 | millimeter |
| foot (ft) | 0.3048 | meter |
| mile (mi) | 1.609 | kilometer |
| | Volume | |
| gallon (gal) | 3.785 | liter |
| | <u>Flow</u> | |
| gallon per minute (gal/min) | 0.06309 | liter per second |
| | SPECIFIC CAPACITY | |
| gallon per minute per foot [(gal/min)/ft] | 0.2070 | liter per second per meter |
| | Pressure | |
| pound per square inch (lb/in ²) | 6.895 | kilopascal |

RESULTS OF BOREHOLE GEOPHYSICAL LOGGING AND AQUIFER-ISOLATION TESTS CONDUCTED IN THE JOHN WAGNER AND SONS, INC. FORMER PRODUCTION WELL, IVYLAND, PENNSYLVANIA

By Ronald A. Sloto

ABSTRACT

A suite of borehole geophysical logs and heatpulse-flowmeter measurements run in the former production well at the John Wagner and Sons, Inc. plant indicate two zones of borehole flow. In the upper part of the well, water enters the borehole through a fracture at 90 ft (feet) below floor level, moves upward, and exits the borehole through a fracture at 72 ft below floor level. Water also enters the borehole through fractures at 205-213, 235, and 357 ft below floor level; moves downward; and exits the borehole through fractures at 450-459, 468-470, and 483-490 ft below floor level. Five zones were selected for aquifer-isolation (packer) tests on the basis of the borehole geophysical logs. The zones were isolated using a straddle-packer assembly. The lowermost three zones (below 248, 223 to 248, and 198 to 223 ft below floor level) were hydraulically isolated from zones above and below. Specific capacities were 0.12, 0.034, and 0.15 gallons per minute per foot, respectively. The hydrograph from zone 2 (223 to 248 ft below floor level) showed interference from a nearby pumping well. For the upper two zones (81 to 106 and 57 to 81 ft below floor level), similar drawdowns in the isolated zone and the zones above and below the isolated zone indicate that these fractures are hydraulically connected outside the borehole in the uncon-fined part of the Stockton Formation. The specific capacity of zones 4 and 5 are similar— 0.82 and 0.61, respectively.

INTRODUCTION

The John Wagner and Sons, Inc. plant is at 900 Jacksonville Road, Ivyland, Pa., adjacent to and north of the U.S. Naval Air Warfare Center in Warminster, Pa. (fig. 1). The well is in a warehouse area inside the plant. The area is underlain by the Stockton Formation. Sloto and others (1996) provide a description of the Stockton Formation in the area.

This report describes the results of borehole geophysical logging and aquifer-isolation tests, commonly known as packer tests, conducted by the U.S. Geological Survey (USGS) in the John Wagner and Sons, Inc. former production well (USGS well BK-2871). This report provides an interpretation of borehole geophysical logs and heatpulse-flowmeter measurements and describes drawdowns, water-level distributions, and specific capacities of isolated fracture zones. The USGS collected the data presented here and prepared this report as part of the environmental hydrogeological investigations at the Warminster Naval Air Warfare Center in cooperation with the U.S. Navy.



Figure 1. Location of the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

RESULTS OF BOREHOLE GEOPHYSICAL LOGGING

A suite of borehole geophysical logs (fig. 2) was run in the well by the USGS. Floor level of the warehouse floor is used as the reference datum in this report. The caliper log shows that the well is 496 ft deep, 6 in. in diameter, and cased to 57 ft below floor level. The fluid-resistivity and fluid-temperature logs show changes in slope at 90, 122, 205, 214, 236, and 355 ft below floor level. A heatpulse flowmeter was used to measure vertical fluid movement in the well under nonpumping conditions. Heatpulse-flowmeter measurements are summarized in table 1. The heatpulse-flowmeter measurements showed upward flow at 80 ft below floor level; no flow at 100, 114, 134, and 198 ft below floor level; and downward flow at 224, 240, 260, 298, 330, 370, 412, 440, 462, and 476 ft below floor level. The suite of borehole geophysical logs and heatpulse-flowmeter measurements indicate that water (0.08 gal/min) enters the borehole through a fracture at 90 ft below floor level, moves upward, and exits the borehole through a fracture at 72 ft below floor level. Water also enters the borehole through fractures at 205-213 (0.14 gal/min), 235 (0.09 gal/min), and 357 (0.09 gal/min) ft below floor level; moves downward; and exits the borehole through fractures at 450-459, 468-470, and 483-490 ft below floor level (fig. 3).



Figure 2. Borehole geophysical logs from the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

Table 1. Summary of heatpulse-flowmeter measurementsmade in the John Wagner and Sons, Inc. former productionwell, Ivyland, Pennsylvania

[--, not measured]

| Depth (feet below floor level) | Flow (gallons per minute) | Flow direction |
|-----------------------------------|------------------------------|-------------------|
| 80 | 0.08 | Up |
| 100 | No flow | |
| 114 | No flow | |
| 134 | No flow | |
| 198 | No flow | |
| 224 | .14 | Down |
| 240 | .23 | Down |
| 260 | .26 | Down |
| 298 | .23 | Down |
| 330 | .20 | Down |
| 370 | .32 | Down |
| 412 | .30 | Down |
| 440 | .32 | Down |
| 462 | .28 | Down |
| 476 | .22 | Down |

RESULTS OF AQUIFER-ISOLATION TESTS

A straddle-packer assembly was used to isolate discrete fracture zones in the Wagner well to determine depth-discrete specific capacity values and to obtain depth-discrete water samples. The maximum inflation pressure of the packers is 190 lb/in², equivalent to the pressure 260 ft below the water surface. The packer assembly consisted of two inflatable packers set on 2in.-diameter lift pipe with a pump set between the packers. The distance from the center of the upper packer to the center of the lower packer was 25 ft. Packer settings given in this report are from the center of the top packer to the center of the bottom packer. Water samples were collected by Brown and Root Environmental, Inc. for volatile organic compound analysis. Water-quality data are presented by Brown and Root Environmental, Inc. (1997).

The packer assembly was lowered to the selected depth in the borehole, and the packers were inflated against the borehole wall, isolating the selected interval. Depths to set packers were based in part on the location of smooth sections of borehole wall determined from the caliper log. Inflation of both packers created three zones-an upper zone above the upper packer, the isolated zone between the packers, and a lower zone below the lower packer (fig. 4B). Pressure in the packers was continuously monitored so that the packers always remained at maximum inflation. Water levels in each zone were measured throughout the tests. Three pressure transducers were used to measure depth to water in the upper, lower, and isolated zones. Data from the transducers were recorded by a data logger at the surface. Measurements also were made during the tests with electric water-level-measurement tapes to verify transducer performance.

On the basis of the borehole geophysical logs and heat-pulse flowmeter measurements, five intervals were selected for aquifer-isolation tests (fig. 5). These intervals are listed in table 2. For the test of the lowermost isolated interval (zone 1), only the upper packer was inflated (fig. 4A). For the test of the uppermost isolated interval (zone 5), only the lower packer was inflated (fig. 4C). For the test of the other intervals (zones 2, 3, and 4), both packers were inflated (fig. 4B).

After the packers were inflated, water levels in each zone were allowed to reach static levels. Water levels were measured with electric tapes for approximately 1 hour unless static levels were reached in a shorter amount of time. After water levels stabilized, a step-drawdown test was run. Each isolated interval was pumped at 2 or 3 pumping rates for 29 to 49 minutes at each rate (table 3). All pumped water was routed through the existing treatment system (activated granular carbon) before being discharged. During the stepdrawdown tests, water levels were recorded above, below, and in the isolated interval. After the pump was shut off, water levels were allowed to recover for approximately 15 minutes before packer deflation.





Figure 3. Caliper log and borehole-flow measurements, John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

The specific capacity of each isolated interval was determined by the following method. The specific capacity for each step was calculated by dividing the average pumping rate during the step by the total drawdown at the end of the step. The specific capacity of the isolated interval is the mean of the specific capacities of each step in the test of the isolated interval.

<u>Aquifer-Isolation Test of Zone 1</u> (248 to 496 Feet Below Floor Level)

For the aquifer-isolation test of zone 1, the center of the upper packer was set at 248 ft below floor level.

Only the upper packer was inflated. Before packer inflation, the depth to water in the open borehole was 6.48 ft below floor level. Fifty-five minutes after packer inflation, the depth to water in the zone above the packer was 5.85 ft below floor level, an increase in water level of 0.63 ft, and the depth to water in the zone below the packer was 16.69 ft below floor level, a decrease in water level of 10.21 ft. This is consistent with the downward borehole-flow measurements, which indicate a higher head in the water-producing fractures in the upper part of the well and a lower head in the water-receiving fractures in the lower part of the well.



NOT TO SCALE

Figure 4. Generalized sketch of straddle-packer assembly and pump in borehole.

ი



Figure 5. Caliper log showing zones isolated in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

| Zone | Depth (feet below floor level) | Reason for selection |
|------|-----------------------------------|---|
| 1 | 248-496 | Water-producing fracture at 357 feet and water-receiving fractures at 450-490 feet |
| 2 | 223-248 | Water-producing fracture at 235 feet, which produces downward flow at 0.09 gallons per minute |
| 3 | 198-223 | Water-producing fractures at 205-213 feet, which produce downward flow at 0.14 gallons per minute |
| 4 | 81-106 | Water-producing fracture at 90 feet, which produces upward flow at 0.08 gallons per minute |
| 5 | 57-81 | Water-receiving fracture at 72 feet |

Table 2. Intervals isolated in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania

Table 3. Pumpage from and specific capacity of isolated zones in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

| Zone | Depth (feet below floor level) | Number of steps | Total water pumped (gallons) | Specific capacity (gallons per minute per foot) |
|------|-----------------------------------|-----------------|------------------------------|---|
| 1 | 248-496 | 2 | 476.5 | 0.12 |
| 2 | 223-248 | 3 | 239.2 | .034 |
| 3 | 198-223 | 2 | 274.6 | .15 |
| 4 | 81-106 | 3 | 476.7 | .82 |
| 5 | 57-81 | 2 | 243.6 | .61 |

The average pumping rate for the first step (table 4) was 5.2 gal/min. The first step was 30 minutes long. The water level in the zone above the packer increased 0.07 ft, and drawdown in the pumped zone below the packer was 38.90 ft. For the second step, the pumping rate was increased to 7.0 gal/min. The second step was 46 minutes long. At the end of the second step, the total increase in water level in the zone above the packer was 0.08 ft, and the total drawdown in the pumped zone below the packer was 61.79 ft. The specific capacity of zone 1 is 0.12 (gal/min)/ft. The hydrographs for the zones above and below the packer are shown in figure 6. The hydrographs indicate no hydraulic connection between the zones.

Table 4. Schedule and pumping rates for the aquifer-isolationtest of zone 1 (248 to 496 feet below floor level) in the JohnWagner and Sons, Inc. former production well, Ivyland,Pennsylvania, December 12, 1996

| Time | Activity |
|------|---|
| 1245 | Begin packer inflation |
| 1340 | Start datalogger (test00) |
| 1345 | Start pump - step 1, average rate = 5.2 gallons per minute |
| 1415 | Increase pumping rate - step 2, average rate = 7.0 gallons per minute |
| 1501 | Pump off |
| 1516 | Begin packer deflation |



Figure 6. Hydrographs from aquifer-isolation test of zone 1 (248 to 496 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

<u>Aquifer-Isolation Test of Zone 2</u> (223 to 248 Feet Below Floor Level)

For the aquifer-isolation test of zone 2, the center of the upper packer was set at 223 ft below floor level; the center of the lower packer was 248 ft below floor level. Before packer inflation, the depth to water in the open borehole was 7.52 ft below floor level. Fifty minutes after packer inflation, the depth to water in the upper zone (zone above the upper packer) was 5.86 ft below floor level, an increase in water level of 1.66 ft; the depth to water in the isolated zone was 5.74 ft below floor level, an increase in water level of 1.78 ft; and the depth to water in the lower zone (zone below the lower packer) was 17.75 ft below floor level, a decrease in water level of 10.23 ft. This is consistent with the downward borehole-flow measurements. which indicated a higher head in the water-producing fractures in the upper part of the well and a lower head in the water-receiving fractures in the lower part of the well.

The average pumping rate for the first step (table 5) was 2.2 gal/min. The first step was 30 minutes long. At the end of the first step, drawdown in the upper zone was 1.57 ft, drawdown in the isolated zone was

62.05 ft, and drawdown in the lower zone was 0.71 ft. For the second step, the pumping rate was increased to 4.3 gal/min. The second step was only 10 minutes long because the water level in the isolated zone quickly dropped to near the depth of the transducer. At the end of the second step, the total drawdown in upper zone was 3.03 ft, the total drawdown in the isolated zone was 102.57 ft, and the total drawdown in the lower zone was 0.85 ft. For the third step, the pumping rate was decreased to 2.6 gal/min. The third step was 49 minutes long. At the end of the third step, the total drawdown in upper zone was 1.35 ft, the total drawdown in the isolated zone was 107.19 ft, and the total drawdown in the lower zone was 0.88 ft. The specific capacity of zone 2 is 0.034 (gal/min)/ft. The hydrographs for the upper zone, isolated zone, and lower zone are shown in figure 7. The hydrographs indicate no hydraulic connection among the three zones. The hydrograph of the isolated zone shows changes in water level not related to the pumping of the Wagner well. These changes in water level probably are caused by the pumping of a nearby industrial well that is hydraulically connected to the isolated zone.

| Time | Activity |
|------|---|
| 0853 | Start datalogger (test02) |
| 0900 | Begin packer inflation |
| 0908 | Packer inflation completed |
| 0946 | Start pump - step 1, average rate = 2.2 gallons per minute |
| 1016 | Increase pumping rate - step 2, average rate = 4.3 gallons per minute |
| 1026 | Decrease pumping rate - step 3, average rate = 2.6 gallons per minute |
| 1115 | Pump off |
| 1132 | Begin packer deflation |
| 1136 | Datalogger off |

Table 5. Schedule and pumping rates for the aquifer-isolation test of zone 2 (223 to 248 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania, December 13, 1996



Figure 7. Hydrographs from aquifer-isolation test of zone 2 (223 to 248 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

Aquifer-Isolation Test of Zone 3 (198 to 223 Feet Below Floor Level)

For the aquifer-isolation test of zone 3, the center of the upper packer was set at 198 ft below floor level; the center of the lower packer was 223 ft below floor level. Before packer inflation, the depth to water in the open borehole was 7.43 ft below floor level. Fifty-eight minutes after packer inflation, the depth to water in the upper zone (zone above the upper packer) was 6.30 ft below floor level, an increase in water level of 1.13 ft; the depth to water in the isolated zone was 4.60 ft below floor level, an increase in water level of 2.83 ft; and the depth to water in the lower zone (zone below the lower packer) was 16.50 ft below floor level, a decrease in water level of 9.07 ft. This is consistent with the downward borehole-flow measurements, which indicated a higher head in the water-producing fractures in the upper part of the well and a lower head in the water-receiving fractures in the lower part of the well.

The average pumping rate for the first step (table 6) was 2.1 gal/min. The first step was 40 minutes long. At the end of the first step, drawdown in the upper zone was 0.17 ft, drawdown in the isolated zone was

11.90 ft, and drawdown in the lower zone was 0.27 ft. For the second step, the pumping rate was increased to 4.8 gal/min. The second step was 40 minutes long. At the end of the second step, the total drawdown in upper zone was 0.18 ft, the total drawdown in the isolated zone was 42.22 ft, and the total drawdown in the lower zone was 0.43 ft. The specific capacity of zone 3 is 0.15 (gal/min)/ft. The hydrographs for the upper zone, isolated zone, and lower zone are shown in figure 8. The hydrographs indicate no hydraulic connection among the three zones.

Aquifer-Isolation Test of Zone 4 (81 to 106 Feet Below Floor Level)

For the aquifer-isolation test of zone 4, the center of the upper packer was set at 81 ft below floor level; the center of the lower packer was 106 ft below floor level. Before packer inflation, the depth to water in the open borehole was 6.23 ft below floor level. Water levels stabilized quickly after packer inflation. At 32 minutes after packer inflation, the depth to water in the upper zone (zone above the upper packer) was 6.24 ft below floor level, an increase in water level of

Table 6. Schedule and pumping rates for the aquifer-isolation test of zone 3 (198 to 223 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania, December 13, 1996

| Ti | ime | Activity |
|----|-----|---|
| 12 | 219 | Begin packer inflation |
| 13 | 316 | Start datalogger (test04) |
| 13 | 320 | Start pump - step 1, average rate = 2.1 gallons per minute |
| 14 | 400 | Increase pumping rate - step 2, average rate = 4.8 gallons per minute |
| 14 | 440 | Pump off |
| 14 | 456 | Begin packer deflation |
| 15 | 500 | Datalogger off |



Figure 8. Hydrographs from aquifer-isolation test of zone 3 (198 to 223 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

0.01 ft; the depth to water in the isolated zone was 6.25 ft below floor level, a decrease in water level of 0.02 ft; and the depth to water in the lower zone (zone below the lower packer) was 6.21 ft below floor level, an increase in water level of 0.02 ft. This indicates little or no difference in head among the three zones and indicates that the zones probably are interconnected. The difference of 0.01 to 0.02 ft may be measurement error.

The average pumping rate for the first step (table 7) was 2.1 gal/min. The first step was 29 minutes long. At the end of the first step, the drawdown in the upper zone was 2.15 ft, the drawdown in the isolated zone was 2.32 ft, and the drawdown in the lower zone was 2.53 ft. For the second step, the pumping rate was increased to 4.6 gal/min. The second step was 30 minutes long. At the end of the second step, the total drawdown in the isolated zone was 5.74 ft, the total drawdown in the lower zone was 5.66 ft. For the third step, the pumping rate was increased to 8.4 gal/min. The third step was 33 minutes long. At the end of the second step, the total drawdown in the lower zone was 5.66 ft. For the third step, the pumping rate was increased to 8.4 gal/min. The third step was 33 minutes long. At the end of the end of the third step, the

the total drawdown in the upper zone was 10.36 ft, the total drawdown in the isolated zone was 11.05 ft, and the total drawdown in the lower zone was 11.01 ft. The specific capacity of zone 4 is 0.82 (gal/min)/ft.

The hydrographs for the upper zone, isolated zone, and lower zone are shown in figure 9. The hydrographs for the three zones are similar, indicating that they are hydraulically connected outside the borehole. The upper part of the Stockton Formation is under unconfined conditions (water table) and is characterized by an interconnected system of fractures (Sloto and others, 1996). Therefore, the specific capacity of zone 4 is greater than that of the isolated fractures.

Aquifer-Isolation Test of Zone 5 (57 to 81 Feet Below Floor Level)

For the aquifer-isolation test of zone 5, the center of the lower packer was set at 81 ft below floor level. The well is cased to 57 ft below floor level. Only the lower packer was inflated, creating two zones, the pumped zone above the lower packer and zone below the lower packer. Before packer inflation, the depth to water in the open borehole was 6.61 ft below floor

| Time | Activity |
|------|---|
| 0913 | Begin packer inflation |
| 0947 | Start datalogger (test06) |
| 1031 | Start pump - step 1, average rate = 2.1 gallons per minute |
| 1100 | Increase pumping rate - step 2, average rate = 4.6 gallons per minute |
| 1130 | Increase pumping rate - step 3, average rate = 8.4 gallons per minute |
| 1203 | Pump off |
| 1221 | Begin packer deflation |
| 1225 | Datalogger off |

Table 7. Schedule and pumping rates for the aquifer-isolation test of zone 4 (81 to 106 feet below floor level) in the

 John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania, December 16, 1996



Figure 9. Hydrographs from aquifer-isolation test of zone 4 (81 to 106 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

level. Water levels stabilized quickly after packer inflation. At 12 minutes after packer inflation, the depth to water above the packer was 6.51 ft below floor level, an increase in water level of 0.08 ft, and the depth to water below the packer was 6.54 ft below floor level, an increase in water level of 0.11 ft. This indicates little or no difference in head between the two zones.

The average pumping rate for the first step (table 8) was 2.3 gal/min. The first step was 33 minutes long. At the end of the first step, drawdown in the pumped zone above the packer was 3.41 ft, and drawdown in the zone below the packer was 2.36 ft. For the second step, the pumping rate was increased to 4.9 gal/min. The second step was 32 minutes long. At the end of the second step, the total drawdown in the pumped zone above the packer was 8.93 ft, and the total drawdown in the zone below the packer was 5.30 ft. The specific capacity of zone 5 is 0.61 (gal/min)/ft. The hydrographs for the zones above and below the packer are shown in figure 10. The hydrographs indicate a hydraulic connection between the two zones outside the borehole. Therefore, the specific capacity of zone 5 is greater than that of the isolated fractures.

SUMMARY AND CONCLUSIONS

A suite of borehole geophysical logs and heatpulse-flowmeter measurements run in the former production well at the John Wagner and Sons, Inc. plant indicate two zones of borehole flow. In the upper part of the well, water enters the borehole through a fracture at 90 ft below floor level, moves upward, and exits the borehole through a fracture at 72 ft below floor level. Water also enters the borehole through fractures at 205-213, 235, and 357 ft below floor level; moves downward; and exits the borehole through fractures at 450-459, 468-470, and 483-490 ft below floor level.

Five zones were selected for aquifer-isolation tests on the basis of interpretation of the borehole geophysical logs run in the well. The zones were isolated using a straddle-packer assembly. The lowermost three zones (below 248, 223 to 248, and 198 to 223 ft below floor level) were hydraulically isolated from zones above and below. Specific capacities were 0.12, 0.034, and 0.15 (gal/min)/ft, respectively. The hydrograph from zone 2 (223 to 248 ft below floor level) showed interference from a nearby pumping well. The isolated zone 81 to 106 ft below floor level (zone 4) isolated a waterproducing fracture at a contact between a sandstone

| Time | Activity |
|------|---|
| 1311 | Start datalogger (test07) |
| 1312 | Begin packer inflation |
| 1327 | Start pump - step 1, average rate = 2.3 gallons per minute |
| 1400 | Increase pumping rate - step 2, average rate = 4.9 gallons per minute |
| 1432 | Pump off |
| 1448 | Begin packer deflation; datalogger off |

Table 8. Schedule and pumping rates for the aquifer-isolation test of zone 5 (57 to 81 feet below floor

 level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania, December 16, 1996



Figure 10. Hydrographs from aquifer-isolation test of zone 5 (57 to 81 feet below floor level) in the John Wagner and Sons, Inc. former production well, Ivyland, Pennsylvania.

and an underlying siltstone. Similar drawdowns in the isolated zone and the zones above and below the isolated zone indicate that this fracture is hydraulically connected with the sandstone above it and the siltstone below it outside the borehole in the unconfined part of the Stockton Formation. Pumping the isolated zone 57 to 81 ft below floor level (zone 5) produced some drawdown in the zone below, indicating a hydraulic connection in the sandstone unit outside the borehole. Zones 4 and 5 are in the unconfined part of the Stockton Formation and have similar specific capacities—0.82 and 0.61, respectively. The specific capacity of zones 4 and 5 is greater than that of the isolated fractures.

REFERENCES CITED

- Brown and Root Environmental, Inc., 1997, NAWC Warminster Wagner well - recommendations, packer sampling and monitoring well water level survey results: Technical Memorandum to the U.S. Navy dated February 26, 1997.
- Sloto, R.A., Macchiaroli, Paola, and Towle, M.T., 1996, Geohydrology of the Stockton Formation and cross-contamination through open boreholes, Hatboro Borough and Warminster Township, Pennsylvania: U.S. Geological Survey Water-Resources Investigations Report 96-4047, 49 p.